

संस्थान के खेल मैदान का सुरक्षा दीवार (Fencing) का कार्य

- **कार्य का विवरण**
संस्थान में स्थित खेल मैदान के चारों ओर 132 मीटर लंबी और 4 फीट ऊंची फेंसिंग का कार्य प्रस्तावित है।
- **आगणन**
 - फेंसिंग की लंबाई: 132 मीटर।
 - फेंसिंग की ऊंचाई: 4 फीट।
 - निर्माण सामग्री: लोहे की जाली (चेन लिंक फेंसिंग) एवं एम एस एंगल पिलर (50 X 50 X 5)। एवं टॉप ओर बॉटम पर एम एस एंगल का साइज (35 X 35 X 5)।
 - एंगल पर पेंट का कार्य भी किया जायेगा
 - बी०ओ०क्यो पृष्ठ 2 में उल्लेखित है।
- **अन्य जानकारी**
 - इच्छुक आवेदकों से अनुरोध है की वह कार्य को भली भांति समझने के लिए साईट का भ्रमण अवश्य करें एवं सामग्री और लेबर की कोटेशन को पृथक-पृथक जमा करें।
 - अधिक जानकारी के लिए सम्पर्क अधिकारी – श्री ज्योति प्रकाश सेमवाल – 91-9719925849
 - बिड जमा करने की अंतिम तिथि - 12.02.2025

BOQ OF PLAY GROUND FENCING IN THDC-IHET B.PURAM

SL. No.	Description	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	9.23	Cum		
2	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40 mm thick with 20 mm nominal size stone aggregate	9.23	Cum		
3	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 25x25 mm made of G.I. wire of dia 3 mm including strengthening with 2 mm dia wire or , welding required complete	596.53	Kg		
4	Providing and fixing MS Angle iron 50x50x5mm including cutting labour, T&P etc complet	1206.24	Kg		
5	Painting with synthetic Enamel Paint of approved brand and manufacture to give and even shade Two coat	22.64	Sqm		
TOTAL					