

BOQ of Roof Repair					
S.No.	Description	Quantity	Unit	Rate	Amount
1	Chipping of Tucking and cleaning of RCC Surface in top of Roof	761.99	Sqm		
2	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40 mm thick with 20 mm nominal size stone aggregate	77.00	Sqm		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:4(1 cement: 4 coarse sand)	1.45	Cum		
4	12 mm cement plaster of mix:1:6 (1 cement: 6 fine sand)	6.3	Sqm		
5	6 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix: 1:3 (1 cement: 3 fine sand)	761.99	Sqm		
6	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. All works above plinth level	2.1	Cum		