

**DETAILED ESTIMATE FOR CONSTRUCTION OF EXPANSION JOINT IN BLOCK-  
E, BLOCK- D, BLOCK- F ,BOYS HOSTEL ,1 & 2 AND GIRLS HOSTEL**

**BOQ**

S.No	Description	Qty	Unit	Rate	Amount
1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40 mm thick with 20 mm nominal size stone aggregate	5.36	Cum		
2	15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand)	88.16	Sqm		
3	Supply & Fixing Of CGI Sheet (plain) In Expansion Joint including cutting placing labour T&P etc complet fittings	574.21	Kg		
4	Supply & Fixing Of S.D Scrow 2.5"	4.00	Box		
				<b>Total</b>	
	Deduction for material Cost (sand & Aggregate)				<b>(-)16771.42</b>
			<b>Net Total</b>		