

**DETAILED ESTIMATE FOR CONSTRUCTION OF WATER PURIFIRE SHED AND FIRE
FIGHTING MOTOR SHED AT ALL THREE HOSTELS**

S.No	Description	Quantity	Unit	Rate	Amount
1	Providing and fixing ISI marked M.S Angle Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position steel etc. For all three sheds.	181.37	Kg		
2	supply& Fixing Mesh jali (15mm X 15mm) wire diameter 1.6mm, (width X length= 4x50) 04 bundel @0.84kg per sq foot for all three sheds	45.61	Kg		
3	Providing Colour Coated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick not less than 275 gm/ m²	26.90	Sqm		
4	Supply & Fixing of fastener used for heavy-duty including Complet Fittings for all three sheds	20.00	No		
5	Painting with synthetic Enamel Paint of approved brand and manufacture to give and even shade Two coat	25.85	Sqm		
6	COST OF 01 PURIFIRE SHED & 01 FIRE FIGHTING MOTOR SHED				
7	TOTAL COST OF THREE SHEDS (03x72331.92)				
	GST 18%				
	TOTAL				
	Total Amount Rs				